


BASIN No. 4
Preliminary Earthwork Exhibit
October 2024



AVE 284



Basin #4 Notes:

Northeast Basin (Priority #2): There is approximately 6.0± feet of material in the north half of the northeast basin.

Northwest Basin (Priority #3): There is approximately 6.0± feet of material to be excavated in the northwest basin &

The contractor shall grade each basin to flow towards the center of each basin. Side slopes shall be graded to a 2:1 and provide a 12' wide access road not greater than 12% into the basin.

The contractor shall perform an independent verification of the amount of material available. The City of Visalia will provide the basin elevations during the excavation process. Contractor is responsible for obtain any and all related permits.

AVE 280