


BASIN No. 3
Preliminary Earthwork Exhibit
October 2024



AVE 288

Rd 68

Area 1: Approximately 8.0± feet of material. Estimated: 46,000 cubic yards.

Area 2: Approximately 8.0± feet of material. Estimated: 50,000 cubic yards.

Area 3: Approximately 1.0± feet of material. Estimated: 19,000 cubic yards.

1,300± ft.

Basin #3 Notes:
Priority #1

Areas 1, 2, & 3 are area to be excavated. Area 1 and Area 2 have approximately 8.0± feet of material to be excavated. Area 3 has approximately 1.0± feet of material to be excavated.

The contractor shall grade each basin to flow towards the northwest corner of this basin. Side slopes shall be graded to a 2:1 and provide a 12' wide access road not greater than 12%.

The contractor shall perform an independent verification of the amount of material available. The City of Visalia will provide the basin elevations during the excavation process.

The contractor to coordinate with Kaweah Delta Water Conservation District and California Department of Fish and Wildlife. Contractor is responsible for obtain any and all related permits.