
# Flood Mitigation and Drought Resiliency Projects at McKay Point "Projects at McKay Point"


March 2022

# Project Site Plan



## Background


- Partnership: Tulare Irrigation District and Consolidated Peoples Ditch Company
- Location: Seaborn Property (old Santa Fe Aggregate mining operation)
  - Approximately 260 acres
  - Mining operations have ended (Lease ends April 2022)
  - Property purchased by Partners in December 2020
- Goals & Objectives:
  - Develop a reservoir to store Kaweah River water for reregulation and flood control
  - Enhance local habitat potential by developing a Habitat Restoration Zone




Riparian

Wetlands

#### Flood Insurance Rate Map Index





### Flood Reduction Zones



Figure 3: Example Inset of an Area Spared from Flooding by the 100- Year Flood along Mill Creek near the East Edge of Visalia. Areas subject to flooding by the 100- year post-condition flood shown in blue. Additional areas subject to flooding by the 100- year pre-condition flood but not the 100- year post-condition flood shown in red. Visalia city limits shown in purple.



Figure 4: Example Inset of an Area Spared from Flooding by the 100- Year Flood near the St. Johns River along the North Edge of Visalia. Areas subject to flooding by the 100- year post-condition flood shown in blue. Additional areas subject to flooding by the 100- year pre-condition flood but not the 100- year post-condition flood shown in red. Visalia city limits shown in purple.

## Engineer's Estimate

### **Building Resilience In Communities**

BRIC '21 Tulare County Drought Resiliency and Flood Mitigation Project At McKay Point

#### PRELIMINARY ENGINEERING ESTIMATE

Cost Estimating

									TID/CPDC		BRIC	Cost Estimating
tem No.	Description		\$/Unit	Unit	Quantity		Subtotal		Cost-Share		Grant	Source
PHASE 1	- Pre Construction											
1.	1 CEQA Compliance	\$	200.00	Hours	500	\$	100,000.00	\$	30,000.00	\$	70,000.00	Experience Estimate <sup>2</sup>
1.3	2 NEPA Compliance	\$	200.00	Hours	250	\$	75,000.00	\$	22,500.00	\$	52,500.00	Experience Estimate <sup>2</sup>
1.3	3 Permits	\$	200.00	Hours	250	\$	50,000.00	\$	15,000.00	\$	35,000.00	Experience Estimate <sup>2</sup>
1.4	4 Project Designs and Specifications	\$	150.00	Hours	667	\$	100,000.00	\$	30,000.00	\$	70,000.00	Experience Estimate <sup>2</sup>
1.	5 Public Construction Bid Offering (go-no-go #1)	\$	150.00	Hours	133	\$	20,000.00	\$	6,000.00	\$	14,000.00	Experience Estimate <sup>2</sup>
PHASE 2	- Construction											
2.	1 Mobilization/Demobilization, Insurance, Permits, Worker Protection	\$	1,140,000.00	1	Each	\$	1,140,000.00	\$	342,000.00	\$	798,000.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	2 Inlet Structure	\$	3,600,000.00	1	Each	\$	3,600,000.00	\$	1,080,000.00	\$	2,520,000.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	3 Gravity/Pressure Pipeline	\$	2,100,000.00	1	Each	\$	2,100,000.00	\$	630,000.00	\$	1,470,000.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	4 Pump Station	\$	2,360,000.00	1	Each	\$	2,360,000.00	\$	708,000.00	\$	1,652,000.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	5 Pump Station Manifold and Discharge	\$	720,000.00	1	Each	\$	720,000.00	\$	216,000.00	\$	504,000.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	6 Earthwork (Cut & Fill) and Habitat Restoration Zone	\$	11,355,000.00	1	Each	\$	11,355,000.00	\$	3,406,500.00	\$	7,948,500.00	Preliminary Engineer's Estimate <sup>3</sup>
2.	7 Construction Management - As Builts (go-no-go #2)	\$	200.00	Hours	900	\$	180,000.00	\$	54,000.00	\$	126,000.00	Experience Estimate <sup>2</sup>
Contingencies (5%) Totals							1,090,000.00 22,890,000.00		327,000.00 6,867,000.00	\$ \$ 1	763,000.00 6,023,000.00	
ercentage	25					*	22,000,000.00	*	30.00%		70.00%	

### Schedule

- Q2 2022 begin RFQ for Engineering/Enviro Consultants
- Q3 2022 Award Engineering/Enviro Consultants Contracts and begin work
- Q2 2024 complete Engineering/Enviro Work and bid construction
- Q2 2024 begin construction
- Q1 2026 complete construction